## HASSAN DIVISION.

*Abstract Notification dated 1st April 1935.*

The attention of the public is invited to pages 834-841, Part VI of the *Mysore Gazette* dated 11th April 1935, calling for sealed tenders up to 27th April 1935 at 3 P.M., for constructing (1) Assistant Superintendent's quarters, (2) Line Inspector's quarters, (3) Linemen's quarters in Hassan District.

---

*Abstract Notification dated 2nd April 1935.*

The attention of the public is invited to pages 840-841, Part VI of the *Mysore Gazette* dated 11th April 1935, publishing the Notification calling for tenders for restoring Chigahally Thattikere Register No. 625 of Hassan Taluk. The last date for receiving the tender is 29th April 1935.

N. LAKSHMINARASIMHAIYA,
*Executive Engineer.*

## KADUR DIVISION.

*Notification dated 12th April 1935.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 2 P.M. on 6th May 1935 for the work of constructing Line Inspector's quarters at Santheveri. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed well before the end of September 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the work of constructing Line Inspectors quarters at Santheveri" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate of the probable cost of constructing a Line Inspectors Quarters (Drawing No. G. 379) at Santhaveri.

| Sl. No. | Items of work | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | Rs. |
| 1 | Earthwork excavation ordinary soil including a lead of 50′ and filling in basement .. | C.yds. | 0 4 6 | 59 | 17 |
| 2(*a*) | Stone jelly concrete in mortar foundations .. | C.ft. | 0 4 6 | 442 | 124 |
| (*b*) | Stone in clay foundation and basement .. | ,, | 0 4 0 | 1,383 | 346 |
| (*c*) | Burnt brick in clay superstructure .. .. | ,, | 0 4 0 | 1,944 | 486 |
| (*d*) | Burnt brick in mortar .. .. .. | ,, | 0 5 3 | 552 | 181 |
| (*e*) | Stone slabs 6″ thick and fixed in mortar .. | S.ft. | 0 14 0 | 171 | 150 |
| (*f*) | Stone slabs 3″ thick and fixed over 'I' beams in verandah .. .. .. .. | ,, | 0 9 0 | 28 | 16 |
| (*g*) | Pointing with mortar basement alround steps . | Sqrs. | 2 8 0 | 2·40 | 6 |
| (*h*) | Plastering with mortar inside bed room etc. .. | ,, | 4 0 0 | 48·22 | 193 |
| (*i*) | White and colour washing as per plastering and pointing .. .. .. .. | ,, | 0 6 0 | 50·62 | 19 |
| (*j*) | Plain cornice 9″ deep front three sides .. | R.ft. | 0 14 0 | 52 | 46 |
| (*k*) | Brick in mortar parapet wall 9″ thick 2½′ height including plastering, etc. .. .. .. | ,, | 1 6 0 | 50 | 69 |
| 3 | Flooring with 1″ cement concrete on a bed of 3″ lime concrete .. .. .. | Sqrs. | 20 0 0 | 8·40 | 168 |
| 4 (*a*) | Mangalore tile roofing front and rear slopes, etc., on teak reepers including fixing, etc., complete .. .. .. .. | ,, | 32 0 0 | 12·03 | 385 |
| (*b*) | Ridge tiles set in mortar .. .. .. | R.ft. | 0 14 0 | 73 | 64 |
| (*c*) | Madras terrace complete .. .. .. | Sqrs. | 37 0 0 | 2·89 | 107 |
| (*d*) | Mathiwood work with oiling .. .. | C.ft. | 4 0 0 | 60 | 240 |
| (*e*) | Plain teakwood Eave Board 9″ .. .. | R.ft. | 0 9 0 | 130 | 73 |
| (*f*) | Doors with teakwood frame and honey wood batten shutters 1″ thick including fixtures.. | S.ft. | 2 0 0 | 163 | 326 |
| (*g*) | Windows with teakwood frame and honey wood battened shutters 1″ thick with iron bars, etc. .. .. .. .. | ,, | 2 4 0 | 110 | 248 |
| (*h*) | Teakwood cup boards with honey wood shutters | S.ft. | 2 0 0 | 48 | 96 |
| 5 | Steel girders fixed complete including painting . | Cwt. | 12 0 0 | 14·80 | 178 |
| 6 | Expanded metal 3″×1½″ with ⅛″ standard with teakwood frame work fixed complete with doorways .. .. .. .. | Sq.ft. | 0 12 0 | 111 | 83 |
| 7 | Chocolate painting 2 coats .. .. | Sqr. | 3 8 0 | 11·17 | 40 |
| 8 | Ventilating tiles (Mangalore Pattern) .. | No. | 2 4 0 | 6 | 14 |
| 9 | Constructing sinks .. .. .. | ,, | 5 0 0 | 2 | 10 |
| 10 | Stone mortar and pestle .. .. .. | ,, | 5 0 0 | 1 | 5 |
| 11 | Chunam border at rear roof .. .. | R.ft. | 0 8 0 | 26 | 13 |
| 12 | Rain water down pipes 3″ dia. fixed .. .. | ,, | 0 6 0 | 50 | 19 |
| 13 | Constructing drain and other sundry works .. | .. | .. | .. | 50 |
| | Total Rupees .. | | | | 3,772 |
| | Contingencies 5% .. | | | | 198 |
| | Grand Total .. | | | | 3,970 |

*Notification dated 12th April 1935.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 2 P.M. on 6th May 1935 for the work of constructing Linemens quarters at Lingenahalli 1¾ blocks. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed well before the end of September 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer the tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the work of constructing Linemens quarters at Lingenahalli 1¾ blocks" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Estimate of the probable cost of constructing one block of Cooly quarters to accommodate four coolies with latrines.

Drawing No. G. 381, 1¾ blocks at Lingenahalli.

| Sl. No. | Items of work | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | |
| 1 | Earth work excavation and filling into basement level .. .. .. .. | C.yd. | 0 4 6 | 33 | 9 |
| 2(*a*) | Stone jelly in lime mortar concrete for foundations .. .. .. .. | C.ft. | 0 4 6 | 287 | 81 |
| (*b*) | Coursed rubble stone masonry in clay foundation and basement .. .. .. .. | ,, | 0 4 0 | 911 | 228 |
| (*c*) | Burnt brick in clay superstructure .. .. | ,, | 0 4 0 | 1,747 | 437 |
| (*d*) | Burnt brick in lime mortar as per deductions above .. .. .. .. | ,, | 0 5 3 | 347 | 114 |
| (*e*) | Stone slabs 4″ thick roughly dressed and set in lime mortar .. .. .. .. | S.ft. | 0 9 0 | 115 | 65 |
| (*f*) | Binding wall 6″×6″ of brick in lime mortar and chunam plastered .. .. .. | C.ft. | 0 5 3 | 28 | 9 |
| (*g*) | Chunam plastering 2 coats .. .. .. | Sqr. | 4 0 0 | 43·15 | 173 |
| (*h*) | Pointing with chunam mortar .. .. | ,, | 2 8 0 | 1·45 | 4 |
| (*i*) | White and colour washing two coats as per plastering and pointing .. .. .. | S.ft. | 0 6 0 | 44·60 | 17 |
| 3(*a*) | Roofing with 1st Class Mangalore Tiles on T.W. reepers 2″×1″ including wood oiling to reepers .. .. .. .. | ,, | 32 0 0 | 13·18 | 422 |
| (*b*) | Ridge tiles set in mortar and cement pointing complete. | R.ft. | 0 14 0 | 68 | 60 |
| (*c*) | Ventilating tiles set in mortar and cement pointed .. .. .. .. | No. | 2 4 0 | 16 | 36 |
| 4 | Honey wood work wrought and put up including wood oiling 2 coats .. .. .. | C.ft. | 4 0 0 | 50·00 | 200 |
| 5(*a*) | Door with teakwood frames and honey wood battens, shutters 1″ thick with fittings, etc., complete .. .. .. .. | S.ft. | 2 0 0 | 78 | 156 |
| (*b*) | Windows with teakwood frames and honey wood battened shutters 1″ thick with iron bars ⅝″ dia. and fitting hinges, etc., complete .. | S.ft. | 2 4 0 | 60 | 135 |

| Sl. No. | Items of work | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | Rs. |
| (c) | Chocolate painting two coats .. .. | Sqr. | 3 8 0 | 3·06 | 11 |
| 6 | Constructing sinks in bath rooms .. .. | No. | 5 0 0 | 4 | 20 |
| 7 | Providing stone mortar and pestle .. .. | ,, | 5 0 0 | 4 | 20 |
| 8 | Constructing drain and other sundry charges .. | L.S. | .. | .. | 23 |
| | Total .. | | | | 2,220 |
| | Contingencies .. | | | | 110 |
| | Grand Total .. | | | | 2,330 |
| | *Latrine.* | | | | |
| 1 | Earth work excavation and filling to basement level .. .. .. .. | C.yd. | 0 4 6 | 4 | 1 |
| 2 (a) | Stone in clay foundation and basement .. | C.ft. | 0 4 0 | 130 | 33 |
| (b) | Burnt brick in mortar superstructure .. | ,, | 0 5 3 | 196 | 64 |
| (c) | Chunam plastering .. .. .. .. | Sqr. | 4 0 0 | 4·91 | 20 |
| (d) | Chunam pointing .. .. .. .. | ,, | 2 8 0 | 0·56 | 1 |
| (e) | White and colour washing 2 coats .. .. | ,, | 0 6 0 | 5·47 | 2 |
| (f) | Cement plastering 1″ thick around interior .. | ,, | 10 0 0 | 0·79 | 8 |
| (g) | Tar washing two coats .. .. .. | ,, | 2 8 0 | 0·63 | 2 |
| 3 | Flooring with 3″ concrete and cement plaster ½″ thick .. .. .. .. | ,, | 20 0 0 | 0·38 | 8 |
| 4 | Fixing outlets constructing drains .. .. | No. | 10 0 0 | 1 | 10 |
| 5 | Providing galvanised iron sheet tubs 12″×6″ complete with tarring .. .. .. | ,, | 0 12 0 | 5 | 4 |
| | Total .. | | | | 153 |
| | Contingencies .. | | | | 7 |
| | Grand Total .. | | | | 160 |
| | Total of the previous sheet 2,330 | | | | |
| | Constructing latrine (as per details enclosed) 160. | | | | |
| | Grand Total Rs. 2,490. | | | | |
| | 1¾ blocks at Lingenahalli 1¾ of 2490=Rs. 4,358. | | | | |

*Notification dated 12th April 1935.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 2 P.M. on 6th May 1935 for the work of constructing Linemens quarters with latrines 2 blocks at Chikmagalur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed well before the end of September 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty only (Rs. 250) in cash or Government Promissory Notes, as earnest money, and be suprescribed "Tender for the work of Constructing Linemen's quarters with latrines at Chikmagalur" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Estimate of the probable cost of constructing one block of Cooly quarters to accommodate four coolies with latrines. Drawing No. G. 381 Two blocks at Chickmagalur.

| Sl. No. | Items of work | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | Rs. |
| 1 | Earthwork excavation and filling into basement level | C.yd. | 0 4 6 | 33 | 9 |
| 2 (*a*) | Stone jelly in lime mortar concrete for foundations | C.ft. | 0 4 6 | 287 | 81 |
| (*b*) | Coursed rubble stone masonry in clay foundation and basement | ,, | 0 4 0 | 911 | 228 |
| (*c*) | Burnt brick in clay superstructure | ,, | 0 4 0 | 1,747 | 437 |
| (*d*) | Burnt brick in lime mortar "as per dudections above" | ,, | 0 5 3 | 347 | 114 |
| (*e*) | Stone slabs 4″ thick roughly dressed and set in lime mortar | S.ft. | 0 9 0 | 115 | 65 |
| (*f*) | binding wall 6″×6″ of brick in lime mortar and chunam plastered | C.ft. | 0 5 3 | 28 | 9 |
| (*g*) | Chunam plastering 2 coats | Sqr. | 4 0 0 | 43·15 | 173 |
| (*h*) | Pointing with chunam mortar | ,, | 2 8 0 | 1·45 | 4 |
| (*i*) | White and colour washing two coats as per plastering and pointing | ,, | 0 6 0 | 44·60 | 17 |
| 3(*a*) | Roofing with 1st Class Mangalore Tiles on teak wood reepers 2″×1″ including wood oiling to reepers | ,, | 32 0 0 | 13·18 | 422 |
| (*b*) | Ridge tiles set in mortar and cement pointing complete | R.ft. | 0 14 0 | 68 | 60 |
| (*c*) | Ventilating tiles set in mortar and cement pointed | No. | 2 4 0 | 16 | 36 |
| 4 | Honey wood work wrought and put up including wood oiling 2 coats | C.ft. | 4 0 0 | 50·00 | 200 |
| 5(*a*) | Door with teakwood frames and honey wood battens, shutters 1″ thick with fittings, etc., complete | S.ft. | 2 0 0 | 78 | 156 |
| (*b*) | Windows with teakwood frames and honey wood battened shutters 1″ thick with iron bars $\frac{5}{8}$″ dia. and fitting hinges, etc., complete | S.ft. | 2 4 0 | 60 | 135 |
| (*c*) | Chocolate painting two coats | Sqr. | 3 8 0 | 3·06 | 11 |
| 6 | Constructing sinks in bath rooms | No. | 5 0 0 | 4 | 20 |
| 7 | Providing stone mortar and pestle | ,, | 5 0 0 | 4 | 20 |
| 8 | Constructing drain and other sundry charges | L.S. | .. | .. | 23 |
| | Total | | | | 2,220 |
| | Contingencies | | | | 110 |
| | Grand Total | | | | 2,330 |

| Sl. No. | Items of work | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | Rs. |
| | *Latrine.* | | | | |
| 1 | Earthwork excavation and filling to basement level .. .. .. .. | C.yd. | 0 4 6 | 4 | 1 |
| 2 (*a*) | Stone in clay foundation and basement .. | C.ft. | 0 4 0 | 130 | 33 |
| (*b*) | Burnt brick in mortar superstructure .. | ,, | 0 5 3 | 196 | 64 |
| (*c*) | Chunam plastering .. .. .. .. | Sqr. | 4 0 0 | 4·91 | 20 |
| (*d*) | Chunam pointing .. .. .. .. | ,, | 2 8 0 | 0·56 | 1 |
| (*e*) | White and colour washing, 2 coats .. .. | ,, | 0 6 0 | 5·47 | 2 |
| (*f*) | Cement plastering ½″ thick all round interior .. | ,, | 10 0 0 | 0·79 | 8 |
| (*g*) | Tar washing, two coats .. .. .. | ,, | 2 8 0 | 0·63 | 2 |
| 3 | Flooring with 3″ concrete and cement plaster ½″ thick .. .. .. .. | ,, | 20 0 0 | 0·38 | 8 |
| 4 | Fixing outlets constructing drains .. .. | No. | 10 0 0 | 1 | 10 |
| 5 | Providing galvanised iron sheet tubs 12″×6″ complete with tarring .. .. .. | No. | 0 12 0 | 5 | 4 |
| | Total .. | | | | 153 |
| | Contingencies .. | | | | 7 |
| | Grand Total .. | | | | 160 |
| | Total of the previous sheet Rs. 2,330. | | | | |
| | Constructing latrine (as per details enclosed) Rs. 160. | | | | |
| | Grand Total Rs. 2,490. | | | | |
| | Two blocks at Chikmagalur 2″ × 2,490 = Rs. 4,980. | | | | |

*Notification dated 12th April 1935.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 2 P.M., on 6th May 1935, for the work of constructing Linemen's quarters with latrines at Santhaveri 2 blocks. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed well before the end of September 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given overleaf, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty only in cash or Government Promissory Notes as earnest money, and be superscribed " Tender for the work of constructing Linemen's quarters with latrines 2 blocks " in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Estimate of the probable cost of constructing one block of Cooly Quarters to accommodate four coolies with latrines. Drawing No. G. 381. Two blocks at Santhaveri.

| Sl. No. | Items of work | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | Rs. |
| 1 | Earthwork excavation and filling into basement level | C.yd. | 0 4 6 | 33 | 9 |
| 2 (*a*) | Stone jelly in lime mortar concrete for foundations | C.ft. | 0 4 6 | 287 | 81 |
| (*b*) | Coarsed rubble stone masonry in clay foundation and basement | ,, | 0 4 0 | 911 | 228 |
| (*c*) | Burnt brick in clay superstructure | ,, | 0 4 0 | 1,747 | 437 |
| (*d*) | Burnt brick in lime mortar as per deductions above | ,, | 0 5 3 | 347 | 114 |
| (*e*) | Stone slabs 4″ thick roughly dressed and set in lime mortar | S.ft. | 0 9 0 | 115 | 65 |
| (*f*) | Binding wall 6″×6″ of brick in lime mortar and chunam plastered | C.ft. | 0 5 3 | 28 | 9 |
| (*g*) | Chunam plastering, 2 coats | Sqr. | 4 0 0 | 43·15 | 173 |
| (*h*) | Pointing with chunam mortar | ,, | 2 8 0 | 1·45 | 4 |
| (*i*) | White and colour washing two coats as per plastering and pointing | ,, | 0 6 0 | 44·60 | 17 |
| 3 | Roofing with 1st class Mangalore tiles on teak wood reepers 2″×1″ including wood-oiling to reepers | ,, | 32 0 0 | 13·18 | 422 |
| (*b*) | Ridge tiles set in mortar and cement pointing, complete | R.ft. | 0 14 0 | 68 | 60 |
| (*c*) | Ventilating tiles set in mortar and cement pointed | No. | 2 4 0 | 16 | 36 |
| | Honeywood work wrought and put up including wood-oiling, 2 coats | C.ft. | 4 0 0 | 50·00 | 200 |
| 5 (*a*) | Door with teakwood frames and honeywood battens, shutters 1″ thick with fittings, etc., complete | S.ft. | 2 0 0 | 78 | 156 |
| (*b*) | Windows with teakwood frames and honeywood battened shutters 1″ thick with iron bars $\frac{5}{8}$″ dia. and fitting hinges, etc., complete | S.ft. | 2 4 0 | 60 | 135 |
| (*c*) | Chocolate painting, two coats | Sqr. | 3 8 0 | 3·06 | 11 |
| 6 | Constructing sinks in bath rooms | No. | 5 0 0 | 4 | 20 |
| 7 | Providing stone mortar and pestle | ,, | 5 0 0 | 4 | 20 |
| 8 | Constructing drain and other sundry charges | L. S. | .. | .. | 23 |
| | Total | | | | 2,220 |
| | Contingencies | | | | 110 |
| | Grand Total | | | | 2,330 |
| | *Latrine.* | | | | |
| 1 | Earthwork excavation and filling to basement level | C.yd. | 0 4 6 | 4 | 1 |
| 2 (*a*) | Stone in clay foundation and basement | C.ft. | 0 4 0 | 130 | 33 |
| (*b*) | Burnt brick in mortar superstructure | ,, | 0 5 3 | 196 | 64 |
| (*c*) | Chunam plastering | Sqr. | 4 0 0 | 4·91 | 20 |
| (*d*) | Chunam pointing | ,, | 2 8 0 | 0·56 | 1 |
| (*e*) | White and colour washing, 2 coats | ,, | 0 6 0 | 5·47 | 2 |
| (*f*) | Cement plastering $\frac{1}{2}$″ thick all round interior | ,, | 10 0 0 | 0·79 | 8 |

| No. | Items of work | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | *Latrine.* | | Rs. a. p. | | |
| (*g*) | Tar washing two coats .. .. .. | Sqr. | 2 8 0 | 0.63 | 2 |
| 3 | Flooring with 3″ concrete and cement plaster ½″ thick .. .. .. .. | ,, | 20 0 0 | 0.38 | 8 |
| 4 | Fixing outlets constructing drains .. .. | No. | 10 0 0 | 1 | 10 |
| 5 | Providing galvanised iron sheet tubs 12″×6″ complete with tarring .. .. .. | ,, | 0 12 0 | 5 | 4 |
| | Total .. | | | | 153 |
| | Contingencies | | | | 7 |
| | Grand Total .. | | | | 160 |
| | Total of the previous sheet Rs. 2,330. Constructing latrine (as per details enclosed) Rs. 160. Grand Total Rs. 2,490. Two blocks at Santhaveri 2×2,490=Rs. 4,980. | | | | |

*Notification dated 12th April 1935.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 2 P.M. on 6th May 1935 for the work of constructing Linemens' quarters at Tarikere—1½ blocks. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed well before the end of September 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and seventy-five in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the work of constructing Linemens' quarters at Tarikere—1½ blocks" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Estimate of the probable cost of constructing one block of Cooly Quarters to accommodate four coolies with latrines. (Drawing No. G. 381).—1½ blocks at Tarikere.

| Sl. No. | Items of work | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | Rs. |
| 1 | Earthwork excavation and filling into basement level | C.yd. | 0 4 6 | 33 | 9 |
| 2 (*a*) | Stone jelly in lime mortar concrete for foundations | C.ft. | 0 4 6 | 287 | 81 |
| (*b*) | Coursed rubble stone masonry in clay foundation and basement | ,, | 0 4 0 | 911 | 228 |
| (*c*) | Burnt brick in clay superstructure | ,, | 0 4 0 | 1,747 | 437 |
| (*d*) | Burnt brick in lime mortar as per deductions above | ,, | 0 5 3 | 347 | 114 |
| (*e*) | Stone slabs 4″ thick roughly dressed and set in lime mortar | S.ft. | 0 9 0 | 115 | 65 |
| (*f*) | Binding wall 6″×6″ of brick in lime mortar and chunam plastered | C.ft. | 0 5 3 | 28 | 9 |
| (*g*) | Chunam plastering 2 coats | Sqr. | 4 0—0 | 43.15 | 173 |
| (*h*) | Pointing with chunam mortar | ,, | 2 8 0 | 1.45 | 4 |
| (*i*) | White and colour washing two coats as per plastering and pointing | ,, | 0 6 0 | 44.60 | 17 |
| 3 | Roofing with 1st Class Mangalore Tiles on teak wood reepers 2″×1″ including wood oiling to reepers | ,, | 32 0 0 | 13.18 | 422 |
| (*b*) | Ridge tiles set in mortar and cement pointing complete | R.ft. | 0 14 0 | 68 | 60 |
| (*c*) | Ventilating tiles set in mortar and cement pointed | No. | 2 4 0 | 16 | 36 |
| 4 | Honey wood work wrought and put up including wood oiling 2 coats | C.ft. | 4 0 0 | 50.00 | 200 |
| 5 (*a*) | Door with teakwood frames and honey wood battens, shutters 1″ thick with fittings, etc., complete | S.ft. | 2 0 0 | 78 | 156 |
| (*b*) | Windows with teakwood frames and honey wood battened shutters 1″ thick with iron bars ⅝″ dia. and fitting hinges, etc., complete | S.ft. | 2 4 0 | 60 | 135 |
| (*c*) | Chacolate painting two coats | Sqr. | 3 8 0 | 3.06 | 11 |
| 6 | Constructing sinks in bath rooms | No. | 5 0 0 | 4 | 20 |
| 7 | Providing stone mortar and pestle | ,, | 5 0 0 | 4 | 20 |
| 8 | Constructing drain and other sundry charges | L. S. | .. | .. | 23 |
| | Total | | | | 2,220 |
| | Contingencies | | | | 110 |
| | Grand Total | | | | 2,330 |
| | *Latrine.* | | | | |
| 1 | Earthwork excavation and filling to basement level | C.yd. | 0 4 6 | 4 | 1 |
| 2 (*a*) | Stone in clay foundation and basement | C.ft. | 0 4 0 | 130 | 33 |
| (*b*) | Burnt brick in mortar superstructure | ,, | 0 5 3 | 196 | 64 |
| (*c*) | Chunam plastering | Sqr. | 4 0 0 | 4.91 | 20 |
| (*d*) | Chunam pointing | ,, | 2 8 0 | 0.56 | 1 |
| (*e*) | White and colour washing 2 coats | ,, | 0 6 0 | 5.47 | 2 |
| (*f*) | Cement plastering ½″ thick all round interior | ,, | 10 0 0 | 0.79 | 8 |
| (*g*) | Tar washing two coats | ,, | 2 8 0 | 0.63 | 2 |
| 3 | Flooring with 3″ concrete and cement plaster ½″ thick | ,, | 20 0 0 | 0.38 | 8 |

| No. | Items of work | Per | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | Rs. a. p. | |
| 4 | Fixing outlets constructing drains .. .. | No. | 10 0 0 | 1 | 10 |
| 5 | Providing galvanised iron sheet tubs 12″×6″ complete with tarring .. .. .. | ,, | 0 12 0 | 5 | 4 |
| | Total .. | | | | 153 |
| | Contingencies .. | | | | 7 |
| | Grand Total .. | | | | 160 |
| | Total of the previous sheet Rs. 2,330. Constructing latrine (as per details enclosed) Rs. 160. Grand Total Rs. 2,490. $1\frac{1}{2}$ blocks at Tarikere $1\frac{1}{2}\times2,490$=Rs. 3,735. | | | | |

*Notification dated 12th April 1935.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 2 P.M. on 6th May 1935, for the work of constructing Line Inspectors' quarters at Chikmagalur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed well before the end of September 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the work of Constructing Line Inspectors' quarters at Chikmagalur" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate of the probable cost of constructing a Line Inspectors' Quarters (Drawing No. G. 379) at Chikmagalur.

| Sl. No. | Items of work | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | Rs. |
| 1 | Earthwork excavation ordinary soil including a lead of 50′ and filling in basement .. | C.yds. | 0 4 6 | 59 | 17 |
| 2 | Stone jelly concrete in mortar foundations .. | C.ft. | 0 4 6 | 442 | 124 |
| (b) | Stone in clay foundation and basement .. | ,, | 0 4 0 | 1,383 | 346 |
| (c) | Burnt brick in clay superstructure .. .. | ,, | 0 4 0 | 1,944 | 486 |
| (d) | Burnt brick in mortar do .. .. | ,, | 0 5 3 | 552 | 181 |
| (e) | Stone slabs 6″ thick and fixed in mortar .. | S.ft. | 0 14 0 | 171 | 150 |
| (f) | Stone slabs 3″ thick and fixed over 'I' beams verandah .. .. .. .. | ,, | 0 9 0 | 28 | 16 |
| (g) | Pointing with mortar basement all round steaps | Sqrs. | 2 8 0 | 2.40 | 6 |
| (h) | Plastering with mortar inside bed room, etc. .. | ,, | 4 0 0 | 48.22 | 193 |
| (i) | White and colour washing as per plastering and pointing .. .. .. .. | ,, | 0 6 0 | 50.62 | 19 |
| (j) | Plain cornice 9″ deep front three sides .. | R.ft. | 0 14 0 | 52 | 46 |
| (k) | Brick in mortar parapet wall 9″ thick 2½′ height including plastering, etc. .. .. | ,, | 1 6 0 | 50 | 69 |
| 3 | Flooring with 1″ cement concrete on a bed of 3″ lime concrete .. .. .. | Sqrs. | 20 0 0 | 8.40 | 168 |
| 4 (a) | Mangalore tile roofing front and rear slopes, etc., on teak reepers including fixing, etc., complete .. .. .. .. | ,, | 32 0 0 | 12.03 | 385 |
| (b) | Ridge tiles set in mortar .. .. .. | R.ft. | 0 14 0 | 73 | 64 |
| (c) | Madras terrace complete .. .. .. | Sqrs. | 37 0 0 | 2.89 | 107 |
| (d) | Mathiwood work with oiling .. .. | C.ft. | 4 0 0 | 60 | 240 |
| (e) | Plain teak wood eve Board 9″ .. .. | R.ft. | 0 9 0 | 130 | 73 |
| (f) | Doors with teak wood frame and honey wood batten shutters 1″ thick including fixtures .. | S.ft. | 2 0 0 | 163 | 326 |
| (g) | Windows with teakwood frame and honey wood battened shutters 1″ thick with iron bars, etc. | ,, | 2 4 0 | 110 | 248 |
| (h) | Teakwood cup boards with honey wood shutters | S.ft. | 2 0 0 | 48 | 96 |
| 5 | Steel girders fixed complete including painting . | Cwt. | 12 0 0 | 14.80 | 178 |
| 6 | Expanded metal 3″×1½″ with ⅛″ standard with teak wood frame work fixed complete with doorways .. .. .. .. | Sq.ft. | 0 12 0 | 111 | 83 |
| 7 | Chacolate painting 2 coats .. .. .. | Sqr. | 3 8 0 | 11.17 | 40 |
| 8 | Ventilating tiles (Mangalore Pattern) .. | No. | 2 4 0 | 6 | 14 |
| 9 | Constructing sinks .. .. .. | ,, | 5 0 0 | 2 | 10 |
| 10 | Stone mortar and pestle .. .. .. | ,, | 5 0 0 | 1 | 5 |
| 11 | Chunam border at rear roof .. .. | R.ft. | 0 8 0 | 26 | 13 |
| 12 | Rain water down pipes 3″ dia fixed .. .. | ,, | 0 6 0 | 50 | 19 |
| 13 | Constructing drain and other sundry works .. | .. | .. | .. | 50 |
| | Total .. | | | | 3,772 |
| | Contingencies 5% .. | | | | 198 |
| | Grand Total .. | | | | 3,970 |

L. A. H. WINCKLER,
*Executive Engineer.*

## CHITALDRUG DIVISION.

*Abstract Notification 30th March 1935.*

The attention of the public is hereby invited to the advertisement on pages 771-772 of the *Mysore Gazette*, dated 4th April 1935, calling for tenders for constructing a building for the Taluk Veterinary Hospital at Hosdurga.

R. THIPPAIYA,
*Executive Engineer.*